Bangalore Electricity Supply Company Limited

No.: BESCOM/NC_LTPWRSA/7174508226/05-07-2021

GSTIN Number: 29AACCB1412G1Z5

Office of
Assistant Executive Engineer
C8 SAHAKARANAGARA
BESCOM
DATE: 05-07-2021

To,
AEE BBMP,
WARD NO,07 B T PURA AMRUTHAHALLI MAIN ROAD

BANGALORE KARNATAKA
560064

Sir/Madam,

Sub: Arranging LT power supply-NEW CONNECTION

Ref: 1) Application No:168194278097 Dated: 02-07-2021
2) Account ID : 3020871215
3) Prevailing KERC regulations.

With reference to your Application No. **168194278097 Dated: 02-07-2021**, power supply to an extent of **3 KW** and **0 HP** on Account ID **3020871215** under LT basis, is hereby sanctioned, subject to the following:

1. Details of your building/premises:

   a. **Plinth area:**

Account ID : 3020871215
Consumer Name : AEE BBMP

Scanned with CamScanner

Scanned by TapScanner

1	No. of Floors Existing	0
2	No. of Floors Added or New	1
3	Existing Plinth Area in sq.m.	0
4	Added or New Plinth Area in sq.m.	15
5	**Total Plinth Area in sq.m.**	15

b. Total height of the building above ground level in m: 3

2. The **PROPOSED** Sanctioned Load of your building is **3 KW**

Existing Load Details of your premises:

1	Existing Sanctioned Load	0
2	New/ Additional Load Required	3 KW and 0 HP
3	Total Load	3 KW

You are requested to pay the following charges by Cash/ DD (above ₹10000/-, only DD will be accepted) in favour of **The Assistant Executive Engineer (EI) C8 SAHAKARANAGARA, BESCOM** within 30 days from the date of this letter:

Sl. No.	Particulars	Amount	CGST	SGST	Total Amount
1.	2 MMD to be for 1 Nos (of 3 **KW** and **0 HP**) installation	₹4070.00	₹0.00	₹0.00	₹4070.00
2.	MSD Amount	₹0.00	₹0.00	₹0.00	₹0.00
3.	Infrastructure Charges	₹0.00	₹0.00	₹0.00	₹0.00
4.	Service Line Cost(Development Charge)	₹0.00	₹0.00	₹0.00	₹0.00
5.	Additional Development /Service Line Charges	₹0.00	₹0.00	₹0.00	₹0.00
	Total				₹4070.00

Note: 2 MMD/MSD shall be paid separately for individual installations (separate Payment Receipts to be drawn).

3. The power supply will be arranged at 230V

4. The Power Tariff applicable to your proposed installation will be **Monthly LT6A tariff schedule for metered customers(BESCOM)** Tariff, or as in force from time to time

5. You have to confirm to purchase High precision/Electrostatic meters/ETV meters of the following capacity:

Account ID : 3020871215

Consumer Name : AEE BBMP

Scanned with CamScanner

Scanned by TapScanner

a) Single Phase Meters _____Nos.

b) Three Phase Meters _____Nos.

c) ETV Meters _____ Nos

d) TP box with _____CTR _____Nos.

6. After the payments, the following requirements may please be fulfilled:

a) Execute agreement of power supply on ₹200/- Stamp Paper in duplicable, for individual installations in the prescribed format

b) Produce necessary License/Permit/No Objection Certificate etc., issued by the Competent Authority, as required under the statute

7(a) The Power supply will be arranged by **BESCOM** as below:

a) From the existing _KVA Transformer

b) After enhancement of TC capacity from KVA to _ KVA of the TC located at

c) After erecting new _ KVA transformer under service connection

7(b) If you intend to install distribution transformer inside your premises, and execute the work under self-execution, to avail above power supply, the following shall be complied:

i. An electrical room with RCC roof having clear floor area of 5 metres X 4 metres, with a vertical clearance of 2.75 meters with locking facility, exhaust fans and adequate size of cable duct, shall be provided at the ground floor, within the Applicant's premises nearer to the main entrance, for installing floor mounted distribution transformer and associated switchgear, or

ii. A clear space of 3 metres X 5 metres open to the sky shall be provided, within the Applicant's premises, preferably at the main entrance, for installing structure mounted distribution transformer and switchgear

8. **BESCOM** approved suitable capacity circuit breaker, ELCB & switchgears shall be used, and all the provisions under KERC Regulations 4.03 and 4.04 shall be complied

9. **BESCOM** reserves the right to cancel power supply and forfeiting of the Deposits paid by you, if the documents submitted by you are found to be fake

10. As per the Govt. Order, solar water heaters of suitable capacity shall be provided

11. Five nos. of Compact Fluorescent Lamps shall be used for each installation

12. The metering equipment to be installed should be conspicuously visible and at the main entrance to the premises, preferably with an independent entrance.

You are requested to contact the undersigned in case of any other information that may be required by you.

We remain at your services.

Yours faithfully

Assistant Executive Engineer

C8 SAHAKARANAGARA

BESCOM

Account ID : 3020871215

Consumer Name : AEE BBMP

Scanned with CamScanner

Scanned by TapScanner

ವಿದ್ಯುತ್ ಸರಬರಾಜು ಕಂಪನಿ ನಿಯಮಿತ

N10-07. BTM Layout. Ammugthalli. D-Low

ಓವರ್ ಹೆಡ್/ಭೂಗತ ಸೇವಾ ಸಂಪರ್ಕಗಳ ಬಿಲ್ ನಮೂನೆ

ತಾಂತ್ರಿಕ ವಿಭಾಗ

(ಕಛೇರಿಯ ಉಪಯೋಗಕ್ಕೆ ಮಾತ್ರ)

೧. ಭದ್ರತಾ ಠೇವಣಿ ರೂ. Nnnn Rs 4070/- ರಶೀದಿ ಸಂಖ್ಯೆ 30908719946O ದಿನಾಂಕ 01/01/2021

೨. ಮೇಲ್ವಿಚಾರಣಾ ಶುಲ್ಕ ರೂ. ..... ರಶೀದಿ ಸಂಖ್ಯೆ ..... ದಿನಾಂಕ .....

೩. ಮಾಪಕ ಭದ್ರತಾ ಠೇವಣಿ ರೂ. ..... ರಶೀದಿ ಸಂಖ್ಯೆ ..... ದಿನಾಂಕ .....

ಮಂಜೂರಾಗಿರುವುದು ರೂ. (ಅ) ..... (ವಿತರಣಾ ಮಾರ್ಗ) + ರೂ. (ಆ) .....

ಒಟ್ಟು ರೂ. .....

ಕಾರ್ಯಾದೇಶ ಸಂಖ್ಯೆ AEE/C8/21-22/14.400/C-19694 ದಿನಾಂಕ 01/01/2021

ಬಡ್ಜೆಟ್ "14,400-ಸಿ.ಡಬ್ಲ್ಯೂ.ಬಿ.ಪಿ.-ಸೇವಾ ಸಂಪರ್ಕಗಳು"

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು (ವಿ.)
ಸಿ-8 ಸಹಕಾರನಗರ ವಿ.ಕಾ.ನಿ.ಉಪವಿಭಾಗ
ದಿನಾಂಕ: 01/01/2021

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು (ವಿ.)
Assistant Executive Engineer (Ele.)
ಸಿ8 ಸಹಕಾರನಗರ ವಿ.ಕಾ.ನಿ.ಉಪವಿಭಾಗ (ವಿ.)
C8 SAHAKARA NAGARA C.O. & M. SUB-DIVISION, BESCOM
ದಿನಾಂಕ 01/01/2021
ಬೆಂಗಳೂರು-560 092/BENGALURU-560 092

ನಿರ್ವಹಣೆ ಮತ್ತು ಪಾಲನೆ ಘಟಕ

ಆರ್. ಆರ್. ಸಂಖ್ಯೆ .....

ಸಂಪರ್ಕ ದಿನಾಂಕ .....

ಇರುವುದು/ಹೊಸದು

ಸಂಪರ್ಕ ವಿಧಾನ : ಓವರ್ ಹೆಡ್/ಭೂಗತ-ಸಿಂಗಲ್ ಫೇಸ್/3 ಫೇಸ್

ಒಟ್ಟೂ ಉದ್ದ .....

ವೆಚ್ಚ ರೂ. ..... (ಅ)

ಅನುಮೋದಿನ ನಮೂದಿಗೆ ಅನುಗುಣವಾಗಿ ಸಂಪರ್ಕ ಮಾರ್ಗ ಹಾಕಲಾಗಿದೆ.

B.S Chidanandaswa
Junior Engineer(Elec.)
unit 20, C3 Sahakaranagara, BESC

ರೆವಿನ್ಯೂ ಶಾಖೆಯ ಉಪಯೋಗಕ್ಕೆ

೧.ಖಾತೆ ಪುಸ್ತಕದಲ್ಲಿ ಖಾತೆ ಆರಂಭಿಸಿದ ದಿನಾಂಕ .....

೨.ಖಾತೆ ಪುಸ್ತಕ ಪುಟ ಸಂಖ್ಯೆ .....

೩.ಮೊದಲನೆ ಬಿಲ್ಲನ್ನು ಕಳುಹಿಸಿದ್ದು .....
ಮೊಬಲಗು ರೂ. .....

೪.ಮಾರ್ಗ ಕನಿಷ್ಠ ಶುಲ್ಕ ರೂ. .....

ಕಿರಿಯ ಸಹಾಯಕ/ಸಹಾಯಕ

ತಾಳೆ ನೋಡಿದೆ

ಹಿರಿಯ ಸಹಾಯಕ/ಸಹಾಯಕ ಲೆಕ್ಕಾಧಿಕಾರಿ

ವಿಭಾಗ ಕಛೇರಿಯ ಉಪಯೋಗಕ್ಕೆ

೧. ಆಸ್ತಿಯ ಮೌಲ್ಯ ರೂ. .....
(ಕಂಪನಿಗೆ ಖರ್ಚು ಹಾಕಬಹುದಾದದ್ದು) ..... (ಅ)
ಮತ್ತು ರೂ. .....
(ಬಳಕೆದಾರರಿಗೆ ಖರ್ಚು ಹಾಕಬಹುದಾದದ್ದು) ..... (ಆ)

ಒಟ್ಟು ರೂ. ..... (ಅ+ಆ)ಗಳನ್ನು ವರ್ಗೀಕರಿಸಲಾಗಿದೆ

೨. ಶ್ರೀ/ಶ್ರೀಮತಿ .....
ಅವರ ಹೆಸರಿಗೆ ರೂ. ..... ಹೊಂದಾಣಿಕೆ
ಮಾಡಲಾಗಿದ್ದು ವಿಭಾಗೀಯ ಲೆಕ್ಕದಲ್ಲಿ ಸೇರಿಸಲಾಗಿದೆ.

ಸಹಾಯಕ/ಹಿರಿಯ ಸಹಾಯಕ

ತಾಳೆ ನೋಡಿದೆ

ಸಹಾಯಕ ಲೆಕ್ಕಾಧಿಕಾರಿ

Scanned by TapScanner

ಆಯಾಜಿಸಿದ ಸಂಪರ್ಕಕ್ಕಾಗಿ ಅಗತ್ಯವಿರುವ ಸಾಮಗ್ರಿಗಳ ವಿವರ (ಅಂದಾಜು ಮೊತ್ತ ಸಹಿತ) ..... ದಿನಾಂಕ .....

ಅರ್ಜಿ ಸಂಖ್ಯೆ LT6 31ww/1105 ಆಯಾಜು ಸಂಖ್ಯೆ 46/2011

ಪ್ರವರ್ಗ ..... ದಿನಾಂಕ 02/04/2012

ಕ್ರಮ ಸಂಖ್ಯೆ	ವಿವರ	ಅಳತೆ ಸಂಖ್ಯೆ	ಘಟಕ	ಅಂದಾಜು ಮೊತ್ತದ ಪ್ರಮಾಣ	ಅಂದಾಜು ಮೊತ್ತ, ಪಾವತಿಸಬೇಕಾದ ಮೊತ್ತ, ಸಾಮಗ್ರಿಗಳ ಬೆಲೆ ಸಹಿತ
೧.	ಮೂಲದ ಸಿ.ಂ. ಫೀಡರ್ 1Ø2-30AYJ105 ಮೂಲದ 3 ಫೀಡರ್ ..... ಆಯ್ದ			1	1000
೨.	ಓವರ್‌ಹೆಡ್ ಮಾರ್ಗದಿಂದ ಪೋಲ್ ಫ್ಲಿಂತ್ ಟೋರ್ಡಿನವರೆಗೆ ಸಂಪರ್ಕಕ್ಕಾಗಿ ವಿದ್ಯುತ್ ಫ್ಲಿಂತ್ ಟೋರ್ಡಾ ಕಟ್‌ಔಟ್ ಒಟ್ಟಾರೆಯಾಗಿ			M/s	500
೩.	ಇತರೆ, ಇನ್ಸೀನಾದರೂ ಇದ್ದರೆ (ವಿವರ ಒದಗಿಸಿ)			ಇತ್ಯಾದಿ, ಸಿ.ಂ. ಫೀಸ್ ರೂ. 400/750 3 ಫೀಸ್ ರೂ. 500/1,000	
೪.	ಮರುಪಾವತಿ ಮಾಡಬೇಕಾದ ಸಂಪರ್ಕ ಮಾರ್ಗದ ಮುಂಚಿನಿಂದ ಹಾಲಿನ ಪೋಲಿಗು				
೪೧.	ವಾತ ಇನ್ಸೀನಾದರೂ ಇದ್ದರೆ				
೫.	ಒಟ್ಟು ಪೊತ್ತ			ಪರಾ	Total 1500

ಸಂಪರ್ಕ ವಿಧಾನ

(ಅ) ಹಾಲಿ ಇರುವ ಸೇವಾ ಮಾರ್ಗ

(ಆ) ಉದ್ದೇಶಿತ ಸಂಪರ್ಕ ಮಾರ್ಗ

(ಇ) ಓವರ್ ಹೆಡ್ ಸಿ.ಂ. ಫೀಸ್/3 ಫೀಸ್

(ಈ) ಭೂಗತ ಕೇಬಲ್ ಸಿ.ಂ. ಫೀಸ್/3 ಫೀಸ್

(ಉ) "ರಸ್ತೆ/ಪಾದಾಚಾರಿ ರಸ್ತೆ ಅಗೆಯುವ ಅಗತ್ಯ ಇದೆಯೇ ಅಥವಾ ಇಲ್ಲವೇ ಸಂಬಂಧಿಸಿದ ಚೌಕದಲ್ಲಿ ಗುರುತು ಮಾಡಿರಿ

*The proposed 4x16 sq.mm cable is laid along the road side/footpath RLC No.12

ದೃಢೀಕರಣ : (ಅಂದಾಜನ್ನು ಸಿದ್ಧಪಡಿಸುವ ಅಧಿಕಾರಿಯು ನೀಡತಕ್ಕದ್ದು)

೧. ಆವರಣವನ್ನು ಪರೀಕ್ಷಿಸಿದ ನಂತರ ನಾನು ಅಂದಾಜನ್ನು ಸಿದ್ಧ ಪಡಿಸಿದ್ದೇನೆ. ಮತ್ತು ಮೂಲದ ಹಲಗೆಯಿಂದ ಸ್ಥಾವರವನ್ನು ನಿಗದಿಪಡಿಸಿ ಬಳಕೆದಾರರಿಗೆ/ಅವರ ಪ್ರತಿನಿಧಿಗಳಿಗೆ ತೋರಿಸಿದ್ದೇನೆ.

೨. ..... ಸಿ.ಂ.ಫೀಸ್/3 ಫೀಸ್ ಗಾತ್ರದ ಓವರ್ ಹೆಡ್/ಭೂಗತ ಸೇವಾ ಮಾರ್ಗವನ್ನು ಹಾಕಬೇಕಾಗಿದೆ. ಹಾಲಿ ಇರುವ ..... ಕೆ.ಡಬ್ಲ್ಯೂ ಒತ್ತಡದಲ್ಲಿಯೇ ಸಿ.ಂ.ಫೀಸ್/3 ಫೀಸ್‌ನ ..... ಗಾತ್ರದ ಓ.ಹೆಡ್/ಭೂಗತ ಕೇಬಲ್ಸ್ ಸೇವಾಮಾರ್ಗದಲ್ಲಿರುವ ಪಿ ..... ಕೆ.ಡಬ್ಲ್ಯೂ ವಿದ್ಯುತ್ತನ್ನು ಹಾಯಿಸಲು ಸಾಧ್ಯವಾಗುತ್ತದೆ.

ಶಾಖಾಧಿಕಾರಿ(ಹೆಸರು ಮತ್ತು ಹುದ್ದೆ)

೩. ..... ವಿ.ಸ.ಕಂ.ನಿ. ನಿರ್ದೇಶನಗಳಿಗೆ ಅನುಗುಣವಾಗಿ ಐ.ಎಸ್.ಐ. ಗುರುತಿಸಿರುವ ಸಿ.ಂ.ಫೀಸ್/3 ಫೀಸ್ ಓವರ್‌ಹೆಡ್/ಭೂಗತ ಸೇವಾ ಕೇಬಲ್‌ಮಾರ್ಗಗಳನ್ನು ಒಳಗೊಂಡಂತೆ ಪೂರ್ಣವಾಗಿ ಕಟ್‌ಔಟ್‌ಗಳನ್ನು ಹಾಕಿಸಲು ಮತ್ತು ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಪಡೆದ ಒಂದು ವರ್ಷದ ಅವಧಿಯಲ್ಲಿ ಸೇವಾಮಾರ್ಗ/ಸಾಮಗ್ರಿಗಳನ್ನು ಗುತ್ತಿಗೆದಾರರ ಮುಖಾಂತರ ನನ್ನ ಸ್ಥಂಭ ಖರ್ಚಿನಲ್ಲಿ ಸರಿಪಡಿಸಲು/ಬದಲಾಯಿಸಲು ಒಪ್ಪಿದ್ದೇನೆ.

೪. ಮೇಲಿನ 4ನೇ ಕ್ರಮಾಂಕದಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ನನಗೆ ಮರುಪಾವತಿ ಮಾಡಬೇಕಾದ ಪೋಲಿಗಾಗಿ ಈ ಸಂಪರ್ಕಕ್ಕೆ ಸಂಬಂಧಿಸಿದ ಹೊಂದಾಣಿಕೆ ಮಾಡಬೇಕಾಗಿ ವಿನಂತಿಸುತ್ತೇನೆ.

Asst. Executive Engineer
Projects Division
Yelahanka Zone
Bangalore

Scanned by TapScanner